



2150 Smithtown Ave., Suite 3, Ronkonkoma, NY 11779
T: 631.580.3191 • F: 631.580.3195 • W: envirohealth.org

January 26, 2017

To: Cold Spring Harbor Central School District

Attached please find the results and remediation response of sampling performed in compliance with the United States Environmental Protection Agency's "3T's for Reducing Lead in Drinking Water in Schools", October, 2006 and New York State Department of Health Subpart 67-4 of Title 10, September 2016.

Sincerely,

A handwritten signature in black ink, appearing to read "Glenn Neuschwender", written in a cursive style.

Glenn Neuschwender
President

DESIGN • INSPECTION • TESTING • ANALYSIS

Lead in Drinking Water Test Results

As of 1/26/17

Sample Location	Fixture Type	1 st Draw Results (ppb)	15 Second Draw Results (ppb)	60 Second Draw Results (ppb)	Remedial Recommendation	Remedial Response	Post Remediation Test Results
Field House	WF	ND	-	-	None	-	-
Womens Locker Room	WF	ND	-	-	None	-	-
Boys Locker Room	WF	ND	-	-	None	-	-
Hallway-Auditorium (S)	WF	ND	-	-	None	-	-
Hallway Auditorium (N)	WF	ND	-	-	None	-	-
"A-12" Hallway	WF	4.64	-	-	None	-	-
"A-19" Hallway	WF	1.41	-	-	None	-	-
Maintenance Area Slop Sink	SS	12.1	-	-	None	SIGN	-
Fitness Center	WF	54.9			FR	REPLACED 5/2/16	
Hallway Main Office	WF	14.4	-	-	None	-	-
Kitchen prep sink	SK	ND	-	-	None	-	-
Cafe	WF	ND	-	-	None	-	-
"HF10" Hallway	WF	ND	-	-	None	-	-
"J-28" Hallway	WF	11.7	-	-	None	-	-
Faculty Hallway	WF	1.23	-	-	None	-	-
Faculty Room	WF	2.44	-	-	None	-	-
"J-7" Hallway	WF	3.19	-	-	None	-	-
"S-1" Hallway	WF	7.77	-	-	None	-	-
Custodian Office	SS	<1.0	-	-	None	-	-
Kitchen Dishwash Station @ (A)	SK	<1.0	-	-	None	-	-
Kitchen Dishwash Station @ (B)	SK	<1.0	-	-	None	-	-
Kitchen Dishwash Station @ (C)	SK	<1.0	-	-	None	-	-
Kitchen Handwash @ (A)	SK	10	-	-	None	-	-

Lead in Drinking Water Test Results

As of 1/26/17

Sample Location	Fixture Type	1 st Draw Results (ppb)	15 Second Draw Results (ppb)	60 Second Draw Results (ppb)	Remedial Recommendation	Remedial Response	Post Remediation Test Results
Kitchen 2 Bay @ (A)	SK	<1.0	-	-	None	-	-
Kitchen 2 Bay @ (B)	SK	3.1	-	-	None	-	-
Outside CAM RM by Kitchen	SP	<1.0	-	-	None	-	-
Kitchen BR @ (A)	SK	4.1	-	-	None	-	-
Kitchen BR @ (B)	SK	2	-	-	None	-	-
Kitchen Coffee Machine	SP	<1.0	-	-	None	-	-
Boiler Room by RM HF10	SS	3.7	-	-	None	-	-
Men's BR by RM HF10 @ (A)	SK	4	-	-	None	-	-
Men's BR by RM HF10 @ (B)	SK	2.9	-	-	None	-	-
Men's BR by RM HF10 @ (C)	SK	4	-	-	None	-	-
Men's BR by RM HF10 @ (D)	SK	7.5	-	-	None	-	-
Men's BR by RM HF10 @ (E)	SK	61			FR	SIGN	
Men's BR by RM HF10 @ (F)	SK	4.2	-	-	None	-	-
Women's BR by RM HF10 @ (A)	SK	1.9	-	-	None	-	-
Women's BR by RM HF10 @ (B)	SK	1.7	-	-	None	-	-
Women's BR by RM HF10 @ (C)	SK	1.9	-	-	None	-	-
Women's BR by RM HF10 @ (D)	SK	2.2	-	-	None	-	-
Women's BR by RM HF10 @ (E)	SK	2.8	-	-	None	-	-
Women's BR by RM HF10 @ (F)	SK	4.7	-	-	None	-	-
Faculty BR at Women's BR	SK	2.1	-	-	None	-	-
RM JS34	SS	<1.0	-	-	None	-	-
RM J18	SK	1.6	-	-	None	-	-
RM J19 Teacher's Station	SK	9.5	-	-	None	-	-

Lead in Drinking Water Test Results

As of 1/26/17

Sample Location	Fixture Type	1 st Draw Results (ppb)	15 Second Draw Results (ppb)	60 Second Draw Results (ppb)	Remedial Recommendation	Remedial Response	Post Remediation Test Results
RM J19 Counter 1 @ (A)	SK	53			FR	SIGN	
RM J19 Counter 1 @ (B)	SK	64			FR	SIGN	
RM J19 Counter 1 @ (C)	SK	63			FR	SIGN	
RM J19 Counter 2	SK	33			FR	SIGN	
RM J19 Counter 3 @ (A)	SK	42			FR	SIGN	
RM J19 Counter 3 @ (B)	SK	26			FR	SIGN	
RM J19 Counter 3 @ (C)	SK	21			FR	SIGN	
Prep RM RM J19/16	SK	43			FR	SIGN	
RM J16 Teacher's Station	SK	23			FR	SIGN	
RM J16 Counter 1 @ (A)	SK	49			FR	SIGN	
RM J16 Counter 1 @ (B)	SK	29			FR	SIGN	
RM J16 Counter 1 @ (C)	SK	39			FR	SIGN	
RM J16 Counter 2	SK	30			FR	SIGN	
RM J16 Counter 3 @ (A)	SK	38			FR	SIGN	
RM J16 Counter 3 @ (B)	SK	57			FR	SIGN	
RM J16 Counter 3 @ (C)	SK	22			FR	SIGN	
Girl's BR by Faculty RM @ (A)	SK	<1.0	-	-	None	-	-
Girl's BR by Faculty RM @ (B)	SK	1.5	-	-	None	-	-
Girl's BR by Faculty RM @ (C)	SK	1.9	-	-	None	-	-
Girl's BR by Faculty RM @ (D)	SK	2.9	-	-	None	-	-
Faculty BR at Girl's BR by Faculty RM	SK	<1.0	-	-	None	-	-
Boy's BR by Faculty RM @ (A)	SK	2	-	-	None	-	-
Boy's BR by Faculty RM @ (C)	SK	2.9	-	-	None	-	-

Lead in Drinking Water Test Results

As of 1/26/17

Sample Location	Fixture Type	1 st Draw Results (ppb)	15 Second Draw Results (ppb)	60 Second Draw Results (ppb)	Remedial Recommendation	Remedial Response	Post Remediation Test Results
Boy's BR by Faculty RM @ (D)	SK	4.3	-	-	None	-	-
Faculty BR at Boy's BR by Faculty RM	SK	5.4	-	-	None	-	-
Faculty RM	SK	1.5	-	-	None	-	-
RM J6 Teacher's Station	SK	31			FR	SIGN	
RM J6 Counter 1 @ (A)	SK	73			FR	SIGN	
RM J6 Counter 1 @ (B)	SK	61			FR	SIGN	
RM J6 Counter 2	SK	6.5	-	-	None	-	-
RM J6 Counter 3	SK	<1.0	-	-	None	-	-
Prep RM J6	SK	40			FR	SIGN	
RM J1 Teacher's Station	SK	25			FR	SIGN	
RM J1 Counter 1	SK	3.6	-	-	None	-	-
RM J1 Counter 2	SK	20			FR	SIGN	
RM J1 Counter 3 @ (A)	SK	22			FR	SIGN	
RM J1 Counter 3 @ (B)	SK	29			FR	SIGN	
Prep RM J1	SK	36			FR	SIGN	
Girl's BR by RM S1 @ (A)	SK	7	-	-	None	-	-
Girl's BR by RM S1 @ (B)	SK	2.5	-	-	None	-	-
Girl's BR by RM S1 @ (D)	SK	1.3	-	-	None	-	-
CC by RM S1	SS	<1.0	-	-	None	-	-
Boy's BR by RM S1 @ (A)	SK	2	-	-	None	-	-
Boy's BR by RM S1 @ (B)	SK	2.9	-	-	None	-	-
RM S1 Teacher's Station	SK	55			FR	SIGN	
RM S1 Counter 1	SK	71			FR	SIGN	

Lead in Drinking Water Test Results

As of 1/26/17

Sample Location	Fixture Type	1 st Draw Results (ppb)	15 Second Draw Results (ppb)	60 Second Draw Results (ppb)	Remedial Recommendation	Remedial Response	Post Remediation Test Results
RM S1 Counter 2	SK	75	-	-	None	-	-
Prep RM S1	SK	72			FR	SIGN	
RM S5 Teacher's Station	SK	50			FR	SIGN	
RM S5 Counter 1 @ (A)	SK	55			FR	SIGN	
RM S5 Counter 1 @ (B)	SK	33			FR	SIGN	
RM S10 Teacher's Station	SK	72			FR	SIGN	
RM S10 Counter 1 @ (A)	SK	85			FR	SIGN	
RM S10 Counter 1 @ (B)	SK	83			FR	SIGN	
RM S10 Counter 1 @ (C)	SK	96			FR	SIGN	
RM S10 Counter 2	SK	94			FR	SIGN	
RM S10 Counter 1 @ (A)	SPRAY	2.3	-	-	None	-	-
RM S10 Fume Hood	SK	34			FR	SIGN	
Prep RM S10.5 Counter (L)	SK	75			FR	SIGN	
Prep RM S10.5 Counter (R)	SK	<1.0	-	-	None	-	-
Prep RM S10.5	SS	6.3	-	-	None	-	-
RM S11 Teacher's Station	SK	78			FR	SIGN	
RM S11 Counter 1	SK	57			FR	SIGN	
RM S11 Counter 2 @ (A)	SK	87			FR	SIGN	
RM S11 Counter 2 @ (B)	SK	72			FR	SIGN	
RM S11 Counter 2 @ (C)	SK	75			FR	SIGN	
Outside RM J 16	SP	46			FR	SIGN	
Outside East Courtyard	SP	6.9	-	-	None	-	-
Outside RM J6 Greenhouse	SP	1.3	-	-	None	-	-

Lead in Drinking Water Test Results

As of 1/26/17

Sample Location	Fixture Type	1 st Draw Results (ppb)	15 Second Draw Results (ppb)	60 Second Draw Results (ppb)	Remedial Recommendation	Remedial Response	Post Remediation Test Results
Outside RM S5	SP	8	-	-	None	-	-
Field House Boys BR	SK	5.3	-	-	None	-	-
Field House Girls BR	SK	4.3	-	-	None	-	-
Field House Boys Basement Office	SK	17			FR	SIGN	
Field House Boys LR BR @ (A)	SK	9.8	-	-	None	-	-
Field House Boys LR BR @ (B)	SK	<1.0	-	-	None	-	-
Field House Boys LR BR @ (C)	SK	2.8	-	-	None	-	-
Field House Boys LR BR @ (D)	SK	4.7	-	-	None	-	-
Field House Boys LR	SS	1.3	-	-	None	-	-
Field House Girls 2nd Floor Office	SK	1.7	-	-	None	-	-
Field House Girls LR BR @ (A)	SK	<1.0	-	-	None	-	-
Field House Girls LR BR @ (B)	SK	2	-	-	None	-	-
Field House Girls LR BR @ (C)	SK	1.4	-	-	None	-	-
Field House Girls LR BR @ (D)	SK	2.7	-	-	None	-	-
Field House Girls LR	SS	6.1	-	-	None	-	-
Field House Athletic Trainer	SK	2.2	-	-	None	-	-
Field House Athletic Trainer	SS	<1.0	-	-	None	-	-
Gymnasium Officials BR	SK	<1.0	-	-	None	-	-
Gymnasium Womens PE Office BR	SK	1.8	-	-	None	-	-
Gymnasium Mens PE Office BR	SK	6.1	-	-	None	-	-
Gymnasium Boys Team Room BR @ (A)	SK	<1.0	-	-	None	-	-
Gymnasium Boys Team Room BR @ (B)	SK	1.2	-	-	None	-	-
Gymnasium Boys Team Room Upper	WF	<1.0	-	-	None	-	-

Lead in Drinking Water Test Results

As of 1/26/17

Sample Location	Fixture Type	1 st Draw Results (ppb)	15 Second Draw Results (ppb)	60 Second Draw Results (ppb)	Remedial Recommendation	Remedial Response	Post Remediation Test Results
Gymnasium Boys Team Room Lower	WF	<1.0	-	-	None	-	-
Gymnasium Girls Team Room BR @ (A)	SK	<1.0	-	-	None	-	-
Gymnasium Girls Team Room BR @ (B)	SK	<1.0	-	-	None	-	-
Gymnasium Girls Team Room Upper	WF	<1.0	-	-	None	-	-
Gymnasium Girls Team Room Lower	WF	<1.0	-	-	None	-	-
CC By Main Electrical Room	SS	8.4	-	-	None	-	-
Mens BR By Auditorium @ (A)	SK	<1.0	-	-	None	-	-
Mens BR By Auditorium @ (B)	SK	<1.0	-	-	None	-	-
Womens BR By Auditorium @ (A)	SK	<1.0	-	-	None	-	-
Womens BR By Auditorium @ (B)	SK	<1.0	-	-	None	-	-
Outside Hose Bib By New Gym	SP	26			FR	SIGN	
BR By M-3	SK	1	-	-	None	-	-
Room A-19 Unit @ (A)	SK	2.1	-	-	None	-	-
Room A-19 Unit @ (B)	SK	1.5	-	-	None	-	-
Room A-14 Teacher's Station	SK	1.2	-	-	None	-	-
Room A-14 Counter	SK	13	-	-	None	-	-
Room A-14 Office	SK	250			FR	SIGN	
Room A-13 Unit @ (A)	SK	14	-	-	None	-	-
Room A-13 Unit @ (B)	SK	8.2	-	-	None	-	-
Room A-6	SK	13	-	-	None	-	-
Room A-6 Unit @ (A)	SK	5.1	-	-	None	-	-
Room A-6 Unit @ (B)	SK	4.4	-	-	None	-	-
Room A-12 Station 1 @ (A)	SK	29			FR	SIGN	

Lead in Drinking Water Test Results

As of 1/26/17

Sample Location	Fixture Type	1 st Draw Results (ppb)	15 Second Draw Results (ppb)	60 Second Draw Results (ppb)	Remedial Recommendation	Remedial Response	Post Remediation Test Results
Room A-12 Station 1 @ (B)	SP	<1.0	-	-	None	-	-
Room A-12 Station 2 @ (A)	SK	3.6	-	-	None	-	-
Room A-12 Station 2 @ (B)	SP	<1.0	-	-	None	-	-
Room A-12 Station 3 @ (A)	SK	5	-	-	None	-	-
Room A-12 Station 3 @ (B)	SP	<1.0	-	-	None	-	-
Room A-12 Station 4 @ (A)	SK	2.2	-	-	None	-	-
Room A-12 Station 4 @ (B)	SP	<1.0	-	-	None	-	-
Room A-12 Station 5 @ (A)	SK	4	-	-	None	-	-
Room A-12 Station 5 @ (B)	SP	<1.0	-	-	None	-	-
Boys BR Arts Wing @ (A)	SK	1.4	-	-	None	-	-
Boys BR Arts Wing @ (B)	SK	<1.0	-	-	None	-	-
Girls BR Arts Wing @ (A)	SK	1.2	-	-	None	-	-
Girls BR Arts Wing @ (B)	SK	2.1	-	-	None	-	-
CC Arts Wing	SS	<1.0	-	-	None	-	-
Mens Faculty BR By Guidance @ (A)	SK	3.2	-	-	None	-	-
Mens Faculty BR By Guidance @ (B)	SK	1.5	-	-	None	-	-
Womens Faculty BR By Guidance @ (A)	SK	6	-	-	None	-	-
Womens Faculty BR By Guidance @ (B)	SK	2.7	-	-	None	-	-
Fitness Center Boiler Room	SS	15	-	-	None	-	-
Room A-11	SK	3.5	-	-	None	-	-
Principal's Kitchen	SK	10	-	-	None	-	-
Nurse's Office	SK	1.7	-	-	None	-	-
Nurse's Office BR	SK	5.5	-	-	None	-	-

Lead in Drinking Water Test Results

As of 1/26/17

Sample Location	Fixture Type	1 st Draw Results (ppb)	15 Second Draw Results (ppb)	60 Second Draw Results (ppb)	Remedial Recommendation	Remedial Response	Post Remediation Test Results
Room S-12 Teacher's Station @ (A)	SK	4.1	-	-	None	-	-
Room S-12 Teacher's Station @ (B)	SK	6.2	-	-	None	-	-
Room S-12 Pod 1 @ (A)	SK	28			FR	SIGN	
Room S-12 Pod 1 @ (B)	SK	34			FR	SIGN	
Room S-12 Pod 2 @ (A)	SK	22			FR	SIGN	
Room S-12 Pod 2 @ (B)	SK	40			FR	SIGN	
Room S-12 Pod 3 @ (A)	SK	16			FR	SIGN	
Room S-12 Pod 3 @ (B)	SK	18			FR	SIGN	
Room S-12 Counter @ (A)	SK	50			FR	SIGN	
Room S-12 Counter @ (B)	SK	39			FR	SIGN	
Room S-12 Counter @ (C)	SK	14	-	-	None	-	-
Room S-12 Counter @ (D)	SK	14	-	-	None	-	-
Room S-12 Counter @ (E)	SK	41			FR	SIGN	
Room S-12 Fume Hood	SK	47			FR	SIGN	
Room S-8	SK	110			FR	SIGN	
Room S-13 Teacher's Station @ (A)	SK	6.4	-	-	None	-	-
Room S-13 Teacher's Station @ (B)	SK	1.6	-	-	None	-	-
Room S-13 Pod 1 @ (A)	SK	19			FR	SIGN	
Room S-13 Pod 1 @ (B)	SK	30			FR	SIGN	
Room S-13 Pod 2 @ (A)	SK	26			FR	SIGN	
Room S-13 Pod 2 @ (B)	SK	27			FR	SIGN	
Room S-13 Pod 3 @ (A)	SK	44			FR	SIGN	
Room S-13 Pod 3 @ (B)	SK	37			FR	SIGN	

Lead in Drinking Water Test Results

As of 1/26/17

Sample Location	Fixture Type	1 st Draw Results (ppb)	15 Second Draw Results (ppb)	60 Second Draw Results (ppb)	Remedial Recommendation	Remedial Response	Post Remediation Test Results
Room S-13 Pod 4 @ (A)	SK	24			FR	SIGN	
Room S-13 Pod 4 @ (B)	SK	20			FR	SIGN	
Room S-13 Counter @ (B)	SK	12	-	-	None	-	-
Room S-13 Counter @ (C)	SK	9.4	-	-	None	-	-
Room S-13 Counter @ (D)	SK	15	-	-	None	-	-
Room S-13 Counter @ (E)	SK	15	-	-	None	-	-
Room S-13 Counter	SPRAY	33			FR	SIGN	
Room S-13 Fume Hood	SK	160			FR	SIGN	
Room S-13 Office	SK	82			FR	SIGN	
Field House Athletic Trainer Office	IM	<1.0	-	-	None	-	-
Outside Athletic Trainer Office	SP	<1.0	-	-	None	-	-

Lead in Drinking Water Test Results

As of 1/26/17

Sample Location	Fixture Type	1 st Draw Results (ppb)	15 Second Draw Results (ppb)	60 Second Draw Results (ppb)	Remedial Recommendation	Remedial Response	Post Remediation Test Results
Hallway by S3 office	WF	1.69	-	-	None	-	-
Room 16	WF	ND	-	-	None	-	-
Room 18	WF	ND	-	-	None	-	-
Room 19	WF	ND	-	-	None	-	-
Room 17	WF	ND	-	-	None	-	-
Hallway Across Facility Room	WF	1.15	-	-	None	-	-
Hallway by C1	WF	1.91	-	-	None	-	-
Room 5	WF	ND	-	-	None	-	-
Room 7	WF	1.41	-	-	None	-	-
Room 9	WF	ND	-	-	None	-	-
Room 11	WF	1.06	-	-	None	-	-
Room 10	WF	5.85	-	-	None	-	-
Room 8	WF	9.58	-	-	None	-	-
Room 6	WF	ND	-	-	None	-	-
Room 4	WF	ND	-	-	None	-	-
Kitchen Pot Filler @ (A)	SK	2.5	-	-	None	-	-
Kitchen Pot Filler @ (B)	SK	6.3	-	-	None	-	-
Kitchen Pot Filler @ (C)	SK	15	-	-	None	-	-
Kitchen Pot Filler @ (D)	SK	1.1	-	-	None	-	-
Kichen Handwash	SK	2.1	-	-	None	-	-
Kitchen Sanitizer Station @ (A)	SK	4.1	-	-	None	-	-
Kitchen Sanitizer Station @ (B)	SK	9.7	-	-	None	-	-

Lead in Drinking Water Test Results

As of 1/26/17

Sample Location	Fixture Type	1 st Draw Results (ppb)	15 Second Draw Results (ppb)	60 Second Draw Results (ppb)	Remedial Recommendation	Remedial Response	Post Remediation Test Results
Kitchen Sanitizer Station @ (C)	SK	11	-	-	None	-	-
Kitchen BR	SK	5.7	-	-	None	-	-
Kitchen Island Prep	SK	43			FR	SIGN	
Business Office BR	SK	14	-	-	None	-	-
CC by Business Office	SS	9	-	-	None	-	-
Business Office Staff Lounge	SK	1	-	-	None	-	-
Men's BR by Employee Benefits	SK	3.3	-	-	None	-	-
Women's BR Employee Benefits	SK	7.5	-	-	None	-	-
Instructional Technology Ladies BR	SK	3	-	-	None	-	-
Superintendent Office BR	SK	16			FR	SIGN	
Music / Community RM	SK	27			FR	SIGN	
Music / Community BR	SK	2.3	-	-	None	-	-
Music / Community RM	WF	1.5	-	-	None	-	-
Women's BR by Board of Edu. RM @ (A)	SK	2.8	-	-	None	-	-
Women's BR by Board of Edu. RM @ (B)	SK	3.6	-	-	None	-	-
Men's BR by Board of Edu. RM	SK	5.5	-	-	None	-	-
Art Room Unit @ (A)	WF	<1.0	-	-	None	-	-
Art Room Unit @ (B)	SK	4.1	-	-	None	-	-
Art Room Unit @ (C)	SK	8.9	-	-	None	-	-
Art Room Unit @ (D)	WF	<1.0	-	-	None	-	-
Art Room BR	SK	4.9	-	-	None	-	-
Resource RM	WF	<1.0	-	-	None	-	-

Lead in Drinking Water Test Results

As of 1/26/17

Sample Location	Fixture Type	1 st Draw Results (ppb)	15 Second Draw Results (ppb)	60 Second Draw Results (ppb)	Remedial Recommendation	Remedial Response	Post Remediation Test Results
Resource RM	SK	13	-	-	None	-	-
Main Offices BR	SK	6.3	-	-	None	-	-
Main Offices Kitchen	SK	5.5	-	-	None	-	-
Boy's BR by C1 @ (A)	SK	2.7	-	-	None	-	-
Boy's BR by C1 @ (B)	SK	<1.0	-	-	None	-	-
CC 1	SS	6.3	-	-	None	-	-
Girl's BR by C1 @ (A)	SK	<1.0	-	-	None	-	-
Girl's BR by C1 @ (B)	SK	<1.0	-	-	None	-	-
Room 5 Combo Unit	SK	1.5	-	-	None	-	-
Room 5 Handwash	SK	8.9	-	-	None	-	-
Room 4	SK	<1.0	-	-	None	-	-
Room 4 BR	SK	3.2	-	-	None	-	-
Room 7	SK	<1.0	-	-	None	-	-
Room 7 BR	SK	<1.0	-	-	None	-	-
Room 6	SK	<1.0	-	-	None	-	-
Room 6 BR	SK	1.6	-	-	None	-	-
Room 9	SK	<1.0	-	-	None	-	-
Room 9 BR	SK	<1.0	-	-	None	-	-
Room 8	SK	3	-	-	None	-	-
Room 8 BR	SK	3.8	-	-	None	-	-
Room 11	SK	<1.0	-	-	None	-	-
Room 11 BR	SK	1.1	-	-	None	-	-

Lead in Drinking Water Test Results

As of 1/26/17

Sample Location	Fixture Type	1 st Draw Results (ppb)	15 Second Draw Results (ppb)	60 Second Draw Results (ppb)	Remedial Recommendation	Remedial Response	Post Remediation Test Results
Room 10	SK	2	-	-	None	-	-
Room 10 BR	SK	3.5	-	-	None	-	-
Faculty Room	SK	<1.0	-	-	None	-	-
Faculty Room BR	SK	5.1	-	-	None	-	-
Stage	SK	45			FR	SIGN	
Book Room BR	SK	8	-	-	None	-	-
Room 12	SK	<1.0	-	-	None	-	-
Room 12 BR	SK	2.6	-	-	None	-	-
S3 Office BR	SK	1.3	-	-	None	-	-
Room 14	SK	<1.0	-	-	None	-	-
Room 14 BR	SK	2	-	-	None	-	-
Room 15	SK	<1.0	-	-	None	-	-
Room 15 BR	SK	6.1	-	-	None	-	-
Room 16	SK	<1.0	-	-	None	-	-
Room 16 BR	SK	<1.0	-	-	None	-	-
Faculty BR by RM 17	SK	2.7	-	-	None	-	-
Room 17	SK	<1.0	-	-	None	-	-
Room 17 BR	SK	6.4	-	-	None	-	-
Room 18	SK	<1.0	-	-	None	-	-
Room 18 BR	SK	<1.0	-	-	None	-	-
Room 19 Combo Unit	SK	<1.0	-	-	None	-	-
Room 19 Handwash	SK	2.3	-	-	None	-	-

Lead in Drinking Water Test Results

As of 1/26/17

Sample Location	Fixture Type	1 st Draw Results (ppb)	15 Second Draw Results (ppb)	60 Second Draw Results (ppb)	Remedial Recommendation	Remedial Response	Post Remediation Test Results
CC by Library	SS	2.4	-	-	None	-	-
Library BR	SK	<1.0	-	-	None	-	-
Nurse's office BR	SK	<1.0	-	-	None	-	-
Nurse's office Handwash	SK	<1.0	-	-	None	-	-
Nurse's office	WF	<1.0	-	-	None	-	-
Nurse's office Combo Unit	SK	<1.0	-	-	None	-	-

Lead in Drinking Water Test Results

As of 1/26/17

Sample Location	Fixture Type	1 st Draw Results (ppb)	15 Second Draw Results (ppb)	60 Second Draw Results (ppb)	Remedial Recommendation	Remedial Response	Post Remediation Test Results
Room 102	WF	ND	-	-	None	-	-
Room 103	WF	ND	-	-	None	-	-
Room 108	WF	4.43	-	-	None	-	-
Room 109	WF	1.16	-	-	None	-	-
Room 107	WF	2.85	-	-	None	-	-
Room 111	WF	ND	-	-	None	-	-
Room 106(S)	WF	ND	-	-	None	-	-
Room 113	WF	1.28	-	-	None	-	-
Room 105	WF	2.13	-	-	None	-	-
Room 115	WF	ND	-	-	None	-	-
Room 104	WF	ND	-	-	None	-	-
Room 118	WF	2.03	-	-	None	-	-
Room 121	WF	ND	-	-	None	-	-
Room 120	WF	ND	-	-	None	-	-
Room 122	WF	2	-	-	None	-	-
Room 123	WF	ND	-	-	None	-	-
Room 124	WF	ND	-	-	None	-	-
Room 125	WF	ND	-	-	None	-	-
Room 126	WF	ND	-	-	None	-	-
Room 127	WF	1.78	-	-	None	-	-
Room 128	WF	ND	-	-	None	-	-
Room 129	WF	ND	-	-	None	-	-

Lead in Drinking Water Test Results

As of 1/26/17

Sample Location	Fixture Type	1 st Draw Results (ppb)	15 Second Draw Results (ppb)	60 Second Draw Results (ppb)	Remedial Recommendation	Remedial Response	Post Remediation Test Results
Hallway by Room 129	WF	ND	-	-	None	-	-
Room 135	WF	ND	-	-	None	-	-
Room 136	WF	ND	-	-	None	-	-
Room 133	WF	ND	-	-	None	-	-
Hallway by Room 134	WF	ND	-	-	None	-	-
Exterior by Room 133	WF	ND	-	-	None	-	-
Hallway by Room 130	WF	1	-	-	None	-	-
Hallway by Room 116	WF	5.79	-	-	None	-	-
Room 106(N)	WF	9.99	-	-	None	-	-
Hallway by Room 106	WF	ND	-	-	None	-	-
Cafeteria	WF	ND	-	-	None	-	-
Hallway by Room 99	WF	1.21	-	-	None	-	-
Kitchen Prep Sink @ (A)	SK	1.4	-	-	None	-	-
Kitchen Prep Sink @ (B)	SK	6.5	-	-	None	-	-
Kitchen Handwash	SK	1.2	-	-	None	-	-
Kitchen Island	SK	3.6	-	-	None	-	-
Kitchen Sanitizer @ (A)	SK	4.6	-	-	None	-	-
Kitchen Sanitizer	SPRAY	<1.0	-	-	None	-	-
Kitchen Sanitizer @ (B)	SK	3.4	-	-	None	-	-
Kitchen BR	SK	<1.0	-	-	None	-	-
Girl's BR by Little Theater	SK	<1.0	-	-	None	-	-
Boy's BR by Little Theater	SK	1.9	-	-	None	-	-

Lead in Drinking Water Test Results

As of 1/26/17

Sample Location	Fixture Type	1 st Draw Results (ppb)	15 Second Draw Results (ppb)	60 Second Draw Results (ppb)	Remedial Recommendation	Remedial Response	Post Remediation Test Results
Sub Office BR	SK	3.2	-	-	None	-	-
Boiler Room	SS	<1.0	-	-	None	-	-
Main Office BR	SK	<1.0	-	-	None	-	-
Main Office Kitchenette	SK	<1.0	-	-	None	-	-
Principal's BR	SK	<1.0	-	-	None	-	-
Nurse's Office	SK	<1.0	-	-	None	-	-
Nurse's Office BR	SK	<1.0	-	-	None	-	-
Dr. Moss' Office BR	SK	<1.0	-	-	None	-	-
Room 102	SK	<1.0	-	-	None	-	-
Room 103	SK	<1.0	-	-	None	-	-
Room 104	SK	<1.0	-	-	None	-	-
Room 105	SK	1.5	-	-	None	-	-
Room 106	SK	<1.0	-	-	None	-	-
Room 106 BR	SK	1.2	-	-	None	-	-
Room 106 by Teacher's Desk	SK	1.5	-	-	None	-	-
CC by RM 107	SS	4	-	-	None	-	-
Room 107	SK	<1.0	-	-	None	-	-
Room 107 BR	SK	<1.0	-	-	None	-	-
Room 108	SK	<1.0	-	-	None	-	-
Room 108 BR	SK	<1.0	-	-	None	-	-
Women's Faculty BR by RM 108	SK	<1.0	-	-	None	-	-
Women's Faculty BR by RM 109	SK	<1.0	-	-	None	-	-

Lead in Drinking Water Test Results

As of 1/26/17

Sample Location	Fixture Type	1 st Draw Results (ppb)	15 Second Draw Results (ppb)	60 Second Draw Results (ppb)	Remedial Recommendation	Remedial Response	Post Remediation Test Results
Room 109	SK	<1.0	-	-	None	-	-
Room 109 BR	SK	<1.0	-	-	None	-	-
Room 111	SK	<1.0	-	-	None	-	-
Room 113	SK	<1.0	-	-	None	-	-
Room 114 Office	SK	2.3	-	-	None	-	-
Room 115	SK	<1.0	-	-	None	-	-
Room 116 @ (A)	SK	<1.0	-	-	None	-	-
Room 116 @ (B)	SK	<1.0	-	-	None	-	-
Room 116 @ (C)	SK	<1.0	-	-	None	-	-
Room 116 @ (D)	SK	1.4	-	-	None	-	-
Room 116 Office	SK	110			FR	SIGN	
CC by RM 116	SS	3.5	-	-	None	-	-
Room 117 Teacher's Station	SK	4.2	-	-	None	-	-
Room 117 Counter @ (A)	SK	2.2	-	-	None	-	-
Room 117 Counter @ (B)	SK	1.4	-	-	None	-	-
Room 117 Office	SK	3.4	-	-	None	-	-
Room 118	SK	<1.0	-	-	None	-	-
Room 120	SK	<1.0	-	-	None	-	-
Unisex BR by RM 119	SK	<1.0	-	-	None	-	-
Room 122	SK	<1.0	-	-	None	-	-
Room 121	SK	<1.0	-	-	None	-	-
Room 123	SK	<1.0	-	-	None	-	-

Lead in Drinking Water Test Results

As of 1/26/17

Sample Location	Fixture Type	1 st Draw Results (ppb)	15 Second Draw Results (ppb)	60 Second Draw Results (ppb)	Remedial Recommendation	Remedial Response	Post Remediation Test Results
Room 124	SK	<1.0	-	-	None	-	-
Room 125	SK	<1.0	-	-	None	-	-
Room 126	SK	<1.0	-	-	None	-	-
Room 127	SK	<1.0	-	-	None	-	-
Room 128	SK	<1.0	-	-	None	-	-
Room 129	SK	<1.0	-	-	None	-	-
CC by RM 129	SS	<1.0	-	-	None	-	-
Girl's BR by RM 129 @ (A)	SK	2.6	-	-	None	-	-
Girl's BR by RM 129 @ (B)	SK	<1.0	-	-	None	-	-
Girl's BR by RM 129 @ (C)	SK	1.6	-	-	None	-	-
Boy's BR by RM 129 @ (A)	SK	2.4	-	-	None	-	-
Boy's BR by RM 129 @ (B)	SK	<1.0	-	-	None	-	-
Boy's BR by RM 129 @ (C)	SK	<1.0	-	-	None	-	-
Room 130 BR	SK	3.5	-	-	None	-	-
Room 131	SK	7.6	-	-	None	-	-
Room 132	SK	<1.0	-	-	None	-	-
CC by RM 134	SS	1.8	-	-	None	-	-
Hallway by RM134-left	WF	<1.0	-	-	None	-	-
Room 133	SK	<1.0	-	-	None	-	-
Unisex BR by RM 134	SK	<1.0	-	-	None	-	-
Library Office	SK	<1.0	-	-	None	-	-
Room 135	SK	<1.0	-	-	None	-	-

Lead in Drinking Water Test Results

As of 1/26/17

Sample Location	Fixture Type	1 st Draw Results (ppb)	15 Second Draw Results (ppb)	60 Second Draw Results (ppb)	Remedial Recommendation	Remedial Response	Post Remediation Test Results
Room 136	SK	<1.0	-	-	None	-	-
Faculty Room	SK	<1.0	-	-	None	-	-
Men's Faculty BR by Faculty RM	SK	<1.0	-	-	None	-	-
Women's Faculty BR by Faculty RM	SK	<1.0	-	-	None	-	-
Cafeteria Bottle Filler	SP	<1.0	-	-	None	-	-
Custodial Office-left	SS	8.8	-	-	None	-	-
Custodial Office-right	SS	4.4	-	-	None	-	-
Outside Spigot in Large Courtyard	SP	23			FR	SIGN	
Outside Spigot by Faculty Room	SP	93			FR	SIGN	
Outside Spigot by RM 134	SP	14	-	-	None	-	-
Outside Spigot by RM 120	SP	2.5	-	-	None	-	-
Outside Spigot in Peace Garden	SP	24			FR	SIGN	
Outside Spigot by RM 116	SP	168			FR	SIGN	
Outside Spigot by RM 109	SP	21			FR	SIGN	
Outside Spigot by Loading Dock	SP	64			FR	SIGN	

Lead in Drinking Water Test Results

As of 1/26/17

Sample Location	Fixture Type	1 st Draw Results (ppb)	15 Second Draw Results (ppb)	60 Second Draw Results (ppb)	Remedial Recommendation	Remedial Response	Post Remediation Test Results
Room 112	WF	2.49	-	-	None	-	-
Room 111	WF	ND	-	-	None	-	-
Room 101	WF	ND	-	-	None	-	-
Room 213	WF	ND	-	-	None	-	-
Room 212	WF	2.85	-	-	None	-	-
Room 208	SK	6.61	-	-	None	-	-
Room 209	SK	8.37	-	-	None	-	-
Room 207	SK	3.26	-	-	None	-	-
Hallway-Room 204	WF	ND	-	-	None	-	-
Hallway-Gym	WF	ND	-	-	None	-	-
Cafe	WF	ND	-	-	None	-	-
Hallway by Nurses Office	WF	8.26	-	-	None	-	-
Hallway-Rm 214	WF	ND	-	-	None	-	-
Hallway-Rm 108	WF	ND	-	-	None	-	-
Room 101	SK	<1.0	-	-	None	-	-
Room 105 Teacher's Station	SK	68			FR	SIGN	
Room 105 Counter @ (A)	SK	170			FR	SIGN	
Room 105 Counter @ (B)	SK	65			FR	SIGN	
Room 105 Counter @ (C)	SK	150			FR	SIGN	
Prep RM 108	SK	73			FR	SIGN	
Boy's BR by RM 105 @ (A)	SK	4.4	-	-	None	-	-
Boy's BR by RM 105 @ (B)	SK	1	-	-	None	-	-

Lead in Drinking Water Test Results

As of 1/26/17

Sample Location	Fixture Type	1 st Draw Results (ppb)	15 Second Draw Results (ppb)	60 Second Draw Results (ppb)	Remedial Recommendation	Remedial Response	Post Remediation Test Results
Hallway RM 108 (Higher)	WF	<1.0	-	-	None	-	-
Girl's BR by RM 108 @ (A)	SK	<1.0	-	-	None	-	-
Girl's BR by RM 108 @ (B)	SK	4.5	-	-	None	-	-
Switch Gear RM by RM 108	SS	<1.0	-	-	None	-	-
Room 111	SK	1.3	-	-	None	-	-
Room 111 BR	SK	4.8	-	-	None	-	-
Room 112	SK	<1.0	-	-	None	-	-
Room 112 BR	SK	3.1	-	-	None	-	-
Book RM by RM 112	SS	5.5	-	-	None	-	-
Room 110 Counter @ (A)	SK	<1.0	-	-	None	-	-
Room 110 Counter @ (B)	SK	<1.0	-	-	None	-	-
Room 214	SK	<1.0	-	-	None	-	-
Room 213	SK	<1.0	-	-	None	-	-
Room 213 BR	SK	<1.0	-	-	None	-	-
Room 212	SK	<1.0	-	-	None	-	-
Room 212 BR	SK	<1.0	-	-	None	-	-
Room 211	SK	23			FR	SIGN	
Room 211 BR	SK	<1.0	-	-	None	-	-
Utility RM by Nurse's Office	SS	<1.0	-	-	None	-	-
Nurse's Office	SK	<1.0	-	-	None	-	-
Nurse's Office BR	SK	<1.0	-	-	None	-	-
Room 210	SK	<1.0	-	-	None	-	-

Lead in Drinking Water Test Results

As of 1/26/17

Sample Location	Fixture Type	1 st Draw Results (ppb)	15 Second Draw Results (ppb)	60 Second Draw Results (ppb)	Remedial Recommendation	Remedial Response	Post Remediation Test Results
Men's BR by Main Entrance	SK	2.9	-	-	None	-	-
Women's BR by Main Entrance	SK	1.2	-	-	None	-	-
Faculty RM 222	SK	<1.0	-	-	None	-	-
GYM BR	SK	1.8	-	-	None	-	-
Kitchen	SPRAY	<1.0	-	-	None	-	-
Kitchen BR	SK	<1.0	-	-	None	-	-
Kitchen Closet	SS	<1.0	-	-	None	-	-
Women's BR by Cafeteria	SK	<1.0	-	-	None	-	-
Girl's BR by Cafeteria	SK	<1.0	-	-	None	-	-
Boy's BR by RM 207	SK	<1.0	-	-	None	-	-
Utility RM by RM 207	SS	5.2	-	-	None	-	-
Girl's BR by RM 207	SK	<1.0	-	-	None	-	-
Boy's BR by RM 205 @ (A)	SK	<1.0	-	-	None	-	-
Boy's BR by RM 205 @ (B)	SK	<1.0	-	-	None	-	-
Utility RM by RM 204	SS	1.6	-	-	None	-	-
Girl's BR by RM 204 @ (A)	SK	3.3	-	-	None	-	-
Girl's BR by RM 204 @ (B)	SK	1.1	-	-	None	-	-
Library Kitchen	SK	2.8	-	-	None	-	-
Room 228 BR	SK	6.1	-	-	None	-	-
Room 202	SK	2.1	-	-	None	-	-
Cafeteria Bottle filler	SP	<1.0	-	-	None	-	-
Outside by Kitchen	SP	9.4	-	-	None	-	-

Lead in Drinking Water Test Results

As of 1/26/17

Sample Location	Fixture Type	1 st Draw Results (ppb)	15 Second Draw Results (ppb)	60 Second Draw Results (ppb)	Remedial Recommendation	Remedial Response	Post Remediation Test Results
Outside by RM 104	SP	3.1	-	-	None	-	-
Outside by Music	SP	14	-	-	None	-	-
Outside by RM 111	SP	230			FR	SIGN	
Outside by Band RM	SP	24			FR	SIGN	
Outside by AIS Patio	SP	520			FR	SIGN	
Outside by Community RM	SP	23			FR	SIGN	